

## SHAKERTOWN CONSTRUCTION

### Advertisement For Bids

Sealed bids for constructing "Site Utilities and Development" work in connection with the proposed Restoration of the Historic Village of Shakertown at Pleasant Hill, Mercer County, Kentucky, will in actual fact be received by the General Contractor for the entire proposed restoration work, Sullivan and Cozart, Inc., 822 W. Kentucky Street, Louisville, Kentucky, and be subject to the approval of the Board of Trustees of the Owner and other interested parties. Bids will be for subcontracts with the General Contractor and will be received at the office of the Owner, 2220 Young Drive, Lexington, Kentucky until 2:00 p.m. Thursday, April 21, 1966, and then at said office publicly opened and read aloud.

The portion of the work for which bids are to be submitted consists of the construction of the work as designated by the following four divisions and approximate quantities:

#### Division B — Sewerage Facilities

Approximately 3,550 linear feet of 8-inch clay sewer pipe, 50 linear feet of 8-inch cast iron sewer pipe, 900 linear feet of 6-inch clay sewer pipe for service connections, 115 linear feet of 6-inch cast iron pipe for service connections, 17 manholes and one 15,000 GPD factory built sewage treatment plant of the extended aeration type.

#### Division C — Water Works Facilities

Approximately 2,350 linear feet of 8-inch Class 150 cast iron pipe and fittings for water lines, 820 linear feet of 6-inch Class 150 cast iron pipe and fittings for water lines, 300 linear feet of 2 $\frac{1}{4}$ -inch Class 150 cast iron pipe and fittings for water lines, 950 linear feet of copper tubing for water lines, necessary gate valves, curb stops and corporation stops, and an 83,000 gallon underground reinforced concrete water storage tank with one 150 GPM domestic water supply pump and two 750 GPM fire service pumps, one with auxiliary diesel engine.